

DESCRIPTION


Insulated FRP Telescopic Earth/Discharge Rod manufactured in fully automatic Pultrusion Plant having strong Electrical & Mechanical Strength.

Options

- Up to 66kV
- Up to 133kV
- Up to 220kV
- Up to 400kV

SPECIFICATIONS

Rods	: 3 (three)
Material	: FRP Pultruded
Process	: Automatic Pultrusion Plant
Surface	: Smooth and Glossy
Design	: Telescopic
Locking	: Push Button type Locking System
Total Sections	: 3
Assembled Length	: 15 feet
H.V. Test	: 110 KV
Glass Content	: 65 %.
Top Section Dia	: 25 mm.
Bottom Section Dia	: 45 mm.
Earthing	: Die cast Aluminium Earthing instrument for 30mm dia
Cable	: 10/25/35 sq. mm. ISI Marked PVC insulated multi-stranded 440/1100V Grade Transparent Copper cable (at extra cost)
Clamp	: Crocodile grounding clamp (one for each rod included, extra available at extra charge)
Cover	: Included



*Technical Specifications & Appearance are subject to change without prior notice